BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2023-24/OW/WORK_INDENT2487

APPROVED SCHEDULE - B

No.EE/BTP/BBMP/KPPP/16/2023-24, Date: 02-02-2024

Name Of Work: Maintenance of water supply works to existing borewells at Thanisandra, Rachenahalli, Vidyasagara and surrounding area in in ward no. 07 (Thanisandra).

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of NARSIMHA K (SREE VIGNESHWARA ENTERPRISES)	
				In Figures	In Words
1	100.00	The lifting of submersible pumpset from well.	Each	1484.85	Rupees One Thousand Four Hundred Eighty Four and Eighty Five Paise Only
2	50.00	The Transportation of pumping machineries	Each	1187.88	Rupees One Thousand One Hundred Eighty Seven and Eighty Eight Paise Only
3	3.00	Rewinding of submersible pumpset with copper winding wires of appropriate guage, as per specifications and / or directions of the departmental officials, including all materials, labour, equipment and testing. for all types of submersible pumpsets etc.(with guarantee period not less than 6 months) For all types of submersible pumpsets above 7.0 HP and upto 7.5H.P.	Each	3800.23	Rupees Three Thousand Eight Hundred and Twenty Three Paise Only
4	14.00	For all types of submersible pumpsets above 10 HP and upto 11 H.P.	Each	5104.92	Rupees Five Thousand One Hundred Four and Ninety Two Paise Only
5	15.00	For all types of submersible pumpsets above 12 HP and upto 13 H.P.	Each	5922.58	Rupees Five Thousand Nine Hundred Twenty Two and Fifty Eight Paise Only
6	14.00	For all types of submersible pumpsets 15HP to 20 HP	Each	8839.83	Rupees Eight Thousand Eight Hundred Thirty Nine and Eighty Three Paise Only
7	20.00	The bowls of same type and make	Each	1484.85	Rupees One Thousand Four Hundred Eighty Four and Eighty Five Paise Only
8	20.00	The Intermediate piece (IP) with IP leaded bronze brush.	Each	1039.39	Rupees One Thousand Thirty Nine and Thirty Nine Paise Only
9	15.00	The upper flange	Each	643.43	Rupees Six Hundred Forty Three and Forty Three Paise Only
10	20.00	Upper/ Lower Housing	Each	1187.88	Rupees One Thousand One Hundred Eighty Seven and Eighty Eight Paise Only
11	14.00	The Guide Vane	Each	692.93	Rupees Six Hundred Ninety Two and Ninety Three Paise Only
12	20.00	The Impeller (Shell moulded with aluminium and bronze.)	Each	1484.85	Rupees One Thousand Four Hundred Eighty Four and Eighty Five Paise Only
13	15.00	The discharge outlet (DO) bearing DO steel brush DO bearing.	Each	2029.30	Rupees Two Thousand Twenty Nine and Thirty Paise Only
14	20.00	The pump shaft made out of stainless steel counterless ground with key way (upto 8 stages).	Each	1484.85	Rupees One Thousand Four Hundred Eighty Four and Eighty Five Paise Only
15	15.00	Pump Couping (Stainless Steel)	Each	1484.85	Rupees One Thousand Four Hundred Eighty Four and Eighty Five Paise Only
16	25.00	Stud and Nuts.	Each	197.98	Rupees One Hundred Ninety Seven and Ninety Eight Paise Only

Signature of Contractor

Executive Engineer

Name Of Work: Maintenance of water supply works to existing borewells at Thanisandra, Rachenahalli, Vidyasagara and surrounding area in in ward no. 07 (Thanisandra).

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of NARSIMHA K (SREE VIGNESHWARA ENTERPRISES)	
				In Figures	In Words
17	15.00	Motor Base With Pin	Each	494.95	Rupees Four Hundred Ninety Four and Ninety Five Paise Only
18	20.00	The Starter of Motor up to 4 to 5 HP	Each	3464.66	Rupees Three Thousand Four Hundred Sixty Four and Sixty Six Paise Only
19	15.00	The Rotor of Motor up to 4 to 5 HP	Each	1979.80	Rupees One Thousand Nine Hundred Seventy Nine and Eighty Paise Only
20	20.00	Carbon Housing	Each	197.98	Rupees One Hundred Ninety Seven and Ninety Eight Paise Only
21	15.00	The Carbon Housing (Thrust bearing block assembly complete with segment bearing pad.	Each	2177.78	Rupees Two Thousand One Hundred Seventy Seven and Seventy Eight Paise Only
22	20.00	Oil Seal Steel Bush	Each	247.47	Rupees Two Hundred Forty Seven and Forty Seven Paise Only
23	15.00	Oil Seal	Each	346.46	Rupees Three Hundred Forty Six and Forty Six Paise Only
24	20.00	The steel bearing bush (DO steel bush)	Each	395.96	Rupees Three Hundred Ninety Five and Ninety Six Paise Only
25	15.00	Allen Screw	Each	1187.88	Rupees One Thousand One Hundred Eighty Seven and Eighty Eight Paise Only
26	20.00	The pump key (stainless steel)	Each	643.43	Rupees Six Hundred Forty Three and Forty Three Paise Only
27	10.00	Nonreturn valve (NRV) assembly complete with rubber O Ring.	Each	643.43	Rupees Six Hundred Forty Three and Forty Three Paise Only
28	20.00	Cable Guard	Each	346.46	Rupees Three Hundred Forty Six and Forty Six Paise Only
29	20.00	Strainer	Each	445.45	Rupees Four Hundred Forty Five and Forty Five Paise Only
30	15.00	Brass Filter	Each	1039.39	Rupees One Thousand Thirty Nine and Thirty Nine Paise Only
31	20.00	Re-erection charges of pumping machineries including overhauling and pointing.	Each	1979.80	Rupees One Thousand Nine Hundred Seventy Nine and Eighty Paise Only
32	20.00	Lock Ring	Each	346.46	Rupees Three Hundred Forty Six and Forty Six Paise Only
33	20.00	The Carbon Housing (Top carbond / ferrodo padding)	Each	346.46	Rupees Three Hundred Forty Six and Forty Six Paise Only
34	14.00	The Gun Metal bearing, centrifugally cast Aluminium Bronze bearing bush	Each	841.41	Rupees Eight Hundred Forty One and Forty One Paise Only
35	20.00	Circillps	Each	197.98	Rupees One Hundred Ninety Seven and Ninety Eight Paise Only
36	30.00	Supplying & fixing of Porcelain fuse channel with cut out onexisting wooden/panel using necessary nuts, bolts and washers complete	Each	396.95	Rupees Three Hundred Ninety Six and Ninety Five Paise Only

K. Narasimha
Signature of Contractor

Executive Engineer

Name Of Work: Maintenance of water supply works to existing borewells at Thanisandra, Rachenahalli, Vidyasagara and surrounding area in in ward no. 07 (Thanisandra).

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of NARSIMHA K (SREE VIGNESHWARA ENTERPRISES)	
				In Figures	In Words
37	300.00	Cutting and threading G.I. pipes for pump fitting, public fountains with appurtenances., where the length of pipe laid is less than 6 metre Pipes of dia 32mm to 80mm	Each	317.67	Rupees Three Hundred Seventeen and Sixty Seven Paise Only
38	150.00	Supply and delivery at site Brand new best make PVC insulated cable of Flat 3 core (sheathed) of nominal cross sectional area as per IS 694-1990 with ISI Mark and as per its latest amendments. 1x3x6 m2	Mtr	183.13	Rupees One Hundred Eighty Three and Thirteen Paise Only
39	10.00	Supply and delivery at site delivery of best indigenous brand new MCB (Miniature Circuit Breakers) of required capacity as per IS 88228/1978 and its latest amendments and with ISI Mark of 6/10/16/20/25/40 Amps with scalable box.	Per 3 Poles	1138.38	Rupees One Thousand One Hundred Thirty Eight and Thirty Eight Paise Only
40	16.88	Earth work excavation for pipeline trenches in all kinds of soils by mechanical means above 600 mm trench width as per drawing and technical specifications, including setting out, construction of shoring, strutting, barricading, caution lights, bracing, using sight rails & boning rods at every 100 mm whevere necessary as directed, removal of stumps and other deleterious matter, dressing of sides and levelling the bottom of trench to the extent required , utilising the available excavated earth locally for the work etc., and all other appurtenances complete in the following strata. Depth exceeding 1.5 m, but not exceeding 3 mPWD	Cum	360.42	Rupees Three Hundred Sixty and Forty Two Paise Only
41	50.00	Providing and installing at site of work P.V.C. pipes including cost of pipes and specials and labour, including lowering into trenches, laying true to line, level and perfect linking at joints leak proof including jointing of approved type with all labour charges and all lift charges, handling charges including encasing the pipe around to a depth not less than 15 cms with gravel or selected earth available from the excavation etc. complete	Mtr	115.81	Rupees One Hundred Fifteen and Eighty One Paise Only
42	16.88	Refilling available earth around trenches/pipelines, cables in layers not exceeding 20 cms in depth, compacting each deposited layer by ramming after watering with a lead upto 50 m , and lift upto 1.5 m. ncluding cost of all labour complete as per specifications	Cum	158.37	Rupees One Hundred Fifty Eight and Thirty Seven Paise Only

K. Narasimha.
Signature of the Contractor

Executive Engineer
Byaravanapura Division
Bruhat Bengaluru Mahanagara Palike